

BRUHAT BANGALORE MAHANAGARA PALIKE

SCHEDULE - B

90

Name of the Work: Improvements to Drains at BEL Layout 3rd Block, 4th Main Road in Ward No. 09
Vidyaranyapura sub Division.

Sl. No.	Approved Qty.	Description	Unit	Schedule-B Rates		
				KRIDL		
				In Figures	Amount	In Words
1	215.22	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	83.16	17897.70	Rupees Eighty Three and Sixteen Paise Only
2	634.50	Removing B.S Slab of Drain and stacking etc complete as per specifications and directions of engineer in charge of the work	Sqm	63.72	40430.34	Rupees Sixty Three and Seventy Two Paise Only
3	634.50	Refixing stone slabs of drains and pointing in C.M (1:3) etc complete as per specifications and directions of engineer in charge of the work	Sqm	78.84	50023.98	Rupees Seventy Eight and Eighty Four Paise Only
4	28.55	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	5070.60	144765.63	Rupees Five Thousand Seventy and Sixty Paise Only
5	35.96	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240 kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	5490.72	197446.29	Rupees Five Thousand Four Hundred Ninety and Seventy Two Paise Only
6	169.20	Providing and constructing precast concrete solid blocks with compressive strength not less than 35 Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x20x20 cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	1018.44	172320.05	Rupees One Thousand Eighteen and Forty Four Paise Only
7	50.76	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 kgs, with 20mm and down size graded granite metal, coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum with superplasticiser @ 3lts confirming to IS 9103-1999 reaffirmed-2008 machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, walls (any thickness) including attached plasters, column, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour, HOM of machinery, curing, etc complete as per specifications and directions of engineer in charge of the work	Cum	6198.12	314616.57	Rupees Six Thousand One Hundred Ninety Eight and Twelve Paise Only

H.V. 1/7/16

S.No.	Improved Qty.	Description	Unit	Schedule-B Rates		
				KRIDL		
				In Figures	Amount	In Words
8	3.05	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 TMT Bars FE 500 etc complete as per specifications and directions of engineer in charge of the work	Tonne	62887.58	191807.12	Rupees Sixty Two Thousand Eight Hundred Eighty Seven and Fifty Eight Paise Only
9	304.56	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work	Sqm	306.72	93414.64	Rupees Three Hundred Six and Seventy Two Paise Only
10	940	Providing and fixing pre cast solid cement concrete kerb stones made out of C.C 1:2:4 with top and bottom width 114 and 165mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting, including formwork curing, including, cost of all materials, labour hire charges of machinery, loading unloading, lead and lift, transportation etc complete as per specifications and directions of engineer in charge of the work	Nos	320.76	301514.40	Rupees Three Hundred Twenty and Seventy Six Paise Only
11	169.20	Providing and applying ready mix priming coat over concrete / masonry / asbestos cement sheet / plastered surfaces including preparing the surface after thoroughly cleaning of oil, grease, dirt and other foreign matter, and sand papering including cost of materials, labour, etc complete as per specifications and directions of engineer in charge of the work	Sqm	27.00	4568.40	Rupees Twenty Seven Only
12	169.20	Providing and applying floor painting with ready mix two coats (Excluding priming coat) on new s concrete / masonry / asbestos cement sheet / / plastered surfaces with flat wall paint of approved brand to give even shade after cleaning the surface of all dirt, dust and other foreign matter, and sand papering including cost of materials, labour, etc complete as per specifications and directions of engineer in charge of the work	Sqm	51.84	8771.33	Rupees Fifty One and Eighty Four Paise Only
13	204.46	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means including loading and unloading. From 0.00 to 11.90 Km etc complete as per specifications and directions of engineer in charge of the work	Cum	106.34	21742.28	Rupees One Hundred Six and Thirty Four Paise Only
Total					1559318.72	

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

11/07

11/7/16

19